

2

DTIC FILE COPY

APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED

REPORT NO. 90-R-04
AFPEA PROJECT NO. 90-P-123

AD-A227 396

Robbin L. Miller
Mechanical Engineer
AUTOVON 787-3362
Commercial (513) 257-3362

DTIC
ELECTE
OCT 05 1990
E D

CONTAINER VARIATION TESTING FOR THE
PREVENTION OF CORROSION

HQ AFLC/DSTZ
AIR FORCE PACKAGING EVALUATION ACTIVITY
Wright-Patterson AFB OH 45433-5999

September 1990

90 10 01 130

NOTICE

When government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related government procurement operation, the United States Government thereby incurs no responsibility whatsoever, and the fact that the government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto. This report is not to be used in whole or in part for advertising or sales purposes.

ABSTRACT

AFPEA recommended
Aerospace Maintenance and Regeneration Center (AMARC), Davis Monthan AFB AZ, requested assistance from the Air Force Packaging Evaluation Activity (AFPEA) in establishing proper packaging procedure for the B-1B Pylon.

The wood crates used to ship and store the B-1B pylons were designed from combined requirements of MIL-STD-26195 and MIL-C-104 and were designed for level C packaging requirements, which indicate immediate use, within three to six months. However, due to the Strategic Arms Limitation Treaty, the pylons were stored in the containers for an extended period of time. As a result of this extended storage, corrosion of the cadmium-plated connector plugs occurred. This corrosion is believed to be the result of formic acid attacking the cadmium-plated parts. The formic acid formation is due to the outgassing of formaldehyde from the wood, combining with water and oxygen.

The decision was made to paint the interior and exterior of the container and to add ventilation in lieu of placing the B-1B pylon inside a barrier bag. A barrier bag was not recommended due to the expense, resealing difficulties, and periodic inspection requirements. *AFPEA recommended*

Tests to identify the best possible combination of container characteristics were recommended by AFPEA so that future programs would not have to involve an educated guess. The results of testing, the test plan devised in accordance with MIL-STD-810D, show that in all cases venting the container led to a higher rate of corrosion than not venting. Additionally, painting the interior of the container did lead to a much lower rate of corrosion. *f*

PREPARED BY:

Robbin Miller
Robbin Miller
Mechanical Engineer
AF Packaging Evaluation Activity

PUBLICATION DATE:

10 SEP 1990

REVIEWED BY:

Ted Hinds
TED HINDS
Chief, Design Branch
AF Packaging Evaluation Activity

APPROVED BY:

Charlie P. Edmonson
CHARLIE P. EDMONSON
Chief, AF Packaging
Evaluation Activity

TABLE OF CONTENTS

ABSTRACT.....	i
TABLE OF CONTENTS.....	ii
INTRODUCTION	
BACKGROUND.....	1
PURPOSE.....	1
DESCRIPTION OF TEST CONTAINER.....	1
TEST OUTLINE AND TEST EQUIPMENT.....	1
TEST PROCEDURE AND RESULTS.....	2
TEST NO. 1, HIGH TEMPERATURE, HIGH HUMIDITY CYCLING TEST.	2
CONCLUSION.....	3
RECOMMENDATIONS.....	3
TABLE 1, CONTAINER TEST PLAN.....	4
FIGURE 1, CONTAINERS.....	5
FIGURE 2, RESEALING WITH DRYWALL SCREWS.....	5
FIGURE 3, PLACEMENT OF TEST LOAD.....	6
FIGURE 4, HUMIDITY CHART AND BULB SETTINGS.....	6
FIGURE 5, TEST RESULTS FOR CONTAINERS 3 AND 6.....	7
FIGURE 6, TEST RESULTS FOR CONTAINERS 1 AND 2.....	7
FIGURE 7, TEST RESULTS FOR CONTAINERS 4 AND 5.....	8
DISTRIBUTION LIST.....	9

CRA&I		<input checked="" type="checkbox"/>
T&B		<input type="checkbox"/>
Unannounced		<input type="checkbox"/>
Justification		
By		
Distribution/		
Availability Codes		
Dist	Avail and/or	
	Special	
A-1		



INTRODUCTION

BACKGROUND: Aerospace Maintenance and Regeneration Center (AMARC), Davis Monthan AFB AZ requested assistance from the Air Force Packaging Evaluation Activity (AFPEA) in establishing proper packaging procedures for the B-1B Pylon.

PURPOSE: The purpose of this testing was to determine which if any of the variations in treatment and venting of the containers would correct the existing problem of corrosion on the cadmium-plated parts, which was apparent during extended storage.

DESCRIPTION OF THE TEST CONTAINERS

DESIGN and CONSTRUCTION: Six 2' x 2' scale models of the cleated plywood containers designed from combined requirements of MIL-STD-26195 and MIL-C-104 were used for testing (see figure 1). Each container weighed 70 pounds. Each container's cover was detachable at the skid, however, the spray painting sealed the cover to the base so the top plate of the container was used for entry and resealed with drywall screws (see figure 2).

TREATMENT and VENTING: Six variations of treatment and venting are outlined below, one container per variation.

TREATMENT	NOW REFERRED TO AS:
NO COATING, VENTED	CONTAINER 6
NO COATING, NOT VENTED	CONTAINER 3
COATED (EXTERIOR ONLY), VENTED	CONTAINER 1
COATED (EXTERIOR ONLY), NOT VENTED	CONTAINER 2
COATED (INTERIOR and EXTERIOR), VENTED	CONTAINER 4
COATED (INTERIOR and EXTERIOR), NOT VENTED	CONTAINER 5

The coating was four to six millimeters of Southwest Paint and Varnish Companies' Kool Coat, a white paint, that is not gas permeable and is resistant to ozone deterioration.

TEST OUTLINE AND TEST EQUIPMENT

TEST PLAN: The test was done in accordance with AFPEA test plan 90-P-123 (see table 1). The test was selected to produce the most favorable conditions of humidity and temperature to enhance corrosion. The test method used was a modified procedure outlined in MIL-STD-810D. The pass/fail criteria was the visual inspection for the presence of corrosion.

TEST LOAD: Two cadmium-plated connector plugs with the cables attached, were placed inside each of the six containers, suspended so that the connector plugs were not in contact with any surface (see figure 3). The plugs were not treated with any preservative. The history and age of these connector plugs are not obtainable and actual B-1B connector plugs were not available due to cost factors.

TEST SITE: All testing was conducted at AFPEA, HQ AFLC/DSTZ. Equipment required for testing is noted in the test plan.

TEST PROCEDURES AND RESULTS

HIGH TEMPERATURE, HIGH HUMIDITY CYCLING TEST: Testing was conducted in accordance with MIL-STD-810D, Method 507.2-7. The cycles were modified to create a more aggravated condition so that test duration was shorter.

RESULTS: At the end of one week of testing, the containers were opened and a visual inspection made of the connector plugs. The inspection revealed definite signs of corrosion on the plugs in containers 3 and 6. Very slight signs of corrosion on the plugs in containers 1,2 and 4 and the plugs in container 5 showed no signs of corrosion. The containers were then resealed and the test resumed. The entire inspection procedure lasted approximately one hour.

At the end of two weeks of testing, the containers were again opened and visual inspection revealed increased corrosion on all plugs. The plugs in containers 3 and 6 had the most corrosion. Plugs in containers 1,2 and 4 showed slightly increased levels of corrosion. The plugs in container 5 showed signs of corrosion just starting. The containers were resealed and the test resumed.

At the end of five weeks the containers were opened and a visual inspection revealed that the levels of corrosion on all plugs had increased. The plugs in container 5 showed the least amount of corrosion. These results are pictured in figures 4,5 and 6. The test was concluded at this time.

CONCLUSION

The container which was coated inside and out (with white paint) and not vented provided the best protection for the cadmium-plated parts against corrosion

RECOMMENDATIONS

The results obtained in this test lead to the conclusion that the proposed resolution may not create the best condition to prevent corrosion on the cadmium-plated parts. It is recommended that future storage containers be painted inside and out but not vented.

Since the history and age of the connector plugs used in this test was not obtainable, it is recommended that the test be repeated with new cadmium-plated parts or test samples/specimens to see if the same results are obtained. It is also recommended that one test sample/specimen in each container be coated with the preservative presently being used on the B1-B pylon. An untreated bare piece of steel (1010 or 1020) and aluminum (6005-T5) should also be placed in the containers, as samples of typical materials shipped and stored, for comparison.

TABLE 1

AIR FORCE PACKAGING EVALUATION ACTIVITY (Container Test Plan)					AFPEA PROJECT NUMBER 90-P-123	
CONTAINER SIZE (L x W x D)(INCHES)		WEIGHT (LBS)		CUBE (CU. FT.)	QUANTITY	DATE
INTERIOR:	EXTERIOR:	GROSS:	ITEM:			
	28 x 26 x 26	70	3	10.9		27 AUG 90
ITEM NAME Cadmium-plated connector plugs				MANUFACTURER		
CONTAINER NAME 2' x 2' CLEATED PLYWOOD BOX					CONTAINER COST	
PACK DESCRIPTION						
CONDITIONING As noted below						
TEST NO.	REF STD/SPEC AND TEST METHOD OR PROCEDURE NO'S	TEST TITLE AND PARAMETERS		CONTAINER ORIENTATION	INSTRUMENTATION	
1.	MIL-STD-810D Method 507.2-7 (modified)	HIGH TEMPERATURE, HIGH HUMIDITY CYCLING TEST 30 day test period. One cycle per day. Constant wet bulb temperature of 117°F. Dry bulb temperature varied as follows: Start at 118°F remain at 118°F for 8 hours. Change dry bulb to 140°F remain at 140°F for 8 hours. Change dry bulb temp to 118°F remain at 118°F for 8 hrs. Repeat last three steps every 24 hours. This causes the humidity to vary from 97% to 51% to 97% respectively.			Instrumentation to verify temperature and humidity readings.	
COMMENTS:						
PREPARED BY: <i>Robbin Miller</i> Robbin Miller Mechanical Engineer				APPROVED BY: <i>Ted Hinds</i> Ted Hinds Chief, Design Br.		

FIGURE 1
CONTAINERS.




FIGURE 2
RESEALING
WITH DRYWALL
SCREWS.



FIGURE 3

PLACEMENT
OF TEST
LOAD.




FIGURE 4

HUMIDITY
CHART AND
BULB
SETTINGS.




FIGURE 5
TEST RESULTS
FOR CONTAINERS
3 AND 6.




FIGURE 6
TEST RESULTS
FOR CONTAINERS
1 AND 2.





FIGURE 7
TEST RESULTS
FOR CONTAINERS
4 AND 5.



DISTRIBUTION LIST

DTIC/FDAC Cameron Station Alexandria, VA 22304-6145	2
HQ USAF/LEYTTC Washington DC 20330	1
HQ AFSC/LGT Andrews AFB DC 20334-5000	1
OC-ALC/DSTD Tinker AFB OK 73145	1
OO-ALC/DSTD Hill AFB UT 84406	1
SA-ALC/DSTD Kelly AFB TX 78241	1
SM-ALC/DSTD McClellan AFB CA 95652	1
WR-ALC/DSTD Robins AFB GA 31098	1
OO-ALC/MMIH Hill AFB UT 84406	2
OO-ALC/MMWR Hill AFB UT 84406	2
GSA, Office of Engineering Mgt Packaging Division Washington DC 20406	1
ASD Det 24/YJA Eglin AFB FL 32542	1
GIDEP Operations Center Corona CA 91720	1
Commander Naval Supply Systems Command Attn: N. Karl (SUP 0611F) Washington DC 20376-5000	1
Commander Naval Air Systems Command Attn: E. Panigot (AIR 41212A) Washington DC 20361	1

DISTRIBUTION LIST (Continued)

Commander Space and Naval Warfare Systems Command Attn: T. Corbe (Code 8218) Washington DC 20360	1
Commander Naval Facilities Engineering Command Hoffman Bldg. #2, Room 12S21 Attn: C. Manwarring (FAC 0644) Alexandria, VA 22332	1
Commanding Officer Naval Construction Battalion Center Attn: K. Pollock (Code 15611K) Port Hueneme, CA 93043	1
Commander Naval Sea Systems Command Attn: F. Basford (SEA 05M3) Washington DC 20362	1
Commanding Officer Naval Aviation Supply Office 700 Robbins Avenue Attn: H. Furlong Philadelphia, PA 19111-5098	1
Commanding Officer Navy Ships Parts Control Center P.O. Box 2020 Attn: F. Sechrst (Code 0541) Mechanicsburg, PA 17055-0788	1
Commanding Officer Naval Air Engineering Center Attn: F. Magnifico (SESD Code 9321) Lakehurst, NJ 08733-5100	1
Commanding Officer Naval Weapons Station, Earle ATTN: NWHC 80A (Mel Gray) NWHC/Code 8023 Colts Neck, NJ 07722-5000	1
US AMC Packaging, Storage, and Containerization Center/SDSTO-TM Tobyhanna, PA 18466-5097	1

DISTRIBUTION LIST (Continued)

AMARC/DS (John Sunay) Davis Monthan AFB AZ 85707-5000	1
ASD/B1LRE Wright-Patterson AFB OH 45433	1
HQ AFLC/DSTZ Library Wright-Patterson AFB OH 45433-5999	10
HQ AFLC/DSTTP (Mark Ferguson) Wright-Patterson AFB OH 45433-5999	1